

**Tender Document**  
**For**  
**Landscaping & Beautification of Indira Chowk, D.D. Chowk & Plantation**  
**Work at Matkota Tiraha to D.D. Chowk, Rudrapur**  
**District-Udham Singh Nagar**



March, 2023

**Tender fees:** Rs. 5900.00 ( GST Including)  
E.M.D.-Rs. 46640.00

District Level Development Authority  
Udham Singh Nagar, Rudrapur  
1<sup>st</sup> Floor, Vikas Bhawan Campus, Rudrapur  
Udham Singh Nagar, Uttarakhand  
[www.ddausn.org.in](http://www.ddausn.org.in)

**Important Dates**

Last date of Accepting Tender	March 06, 2023, by or before 2:00 PM
Date of opening of Tender	March 06, 2023 at 3:00 PM or thereafter




## **TENDER'S DETAIL**

<b>Name of Work-</b>	Landscaping & Beautification of Indira Chowk, D.D. Chowk & Plantation Work at Matkota Tiraha to D.D. Chowk, Rudrapur
<b>Location of Work-</b>	Rudrapur
<b>Estimated Cost of Work</b>	Rs. 23,31,915.00
<b>E.M.D.</b>	Rs. 46640.00
<b>Date of Accepting Tender</b>	06.03.2023 up to 2:00 PM
<b>Date of Opening Tender -</b>	06.03.2023 at 3:00 PM or thereafter
<b>Validity of Tender-</b>	30 days
<b>Time for Completion-</b>	15 Days from the date of Agreement.

## CONTRACTOR DETAILS

1.	Name of Contractor	
2.	Address	
3.	Tel./Mob. Number	
4.	PAN No.	-
5.	G. S. T. No.	-
6.	Copy of Income Tax return (Last Financial year )	-
7.	Tender Fees Detail in the form of Draft / Cash Receipt	Draft No./Cash Receipt Date
8.	Earnest Money Detail	FDR/NSC No. Date Name of Bank
9.	Affidavit of Rs. 100.00 regarding not been black listed in any Govt. / Private organization.(if attached Please tick)	
10.	Stamp paper of Rs. 100, with 1.00 Rs. Revenue Stamp (if attached Please tick)	
11.	Attached a Certified copy of similar Horticulture work done or ongoing works in any Development Authority of Uttarakhand or under government / semi government organization of Uttarakhand.	

Signature of Contractor





## GENERAL CONDITIONS

1. All work shall be carried out as per PWD specifications.
2. GPW form 9 shall be part of the agreement and all conditions shall be binding on the contractor.
3. The quantities worked out in estimate are liable to variation for which no claim whatsoever shall be entertained by the department.
4. The rate shall be inclusive of cost of all materials, royalty, all T & P, octroi, tax, carriage, stacking lead and lift etc.
5. While quoting their rates tenderers are advised to take into account fluctuations in market rates. No claim will be entertained on this account during acceptance of the tender and duration of the contract including extended period for completion of work. Rate should include lead of all material, royalty where payable and water arrangements and all local taxes including sales taxes and other taxes as toll etc.
6. Tenderer are advised to see site of work and acquaint themselves with locality and availability of labour and position of materials, conditions of contract, drawing and specification before tendering.
7. In case of firm, tenders must be signed by each partner or member of the person holding the power of attorney.
8. If required the contractor shall provide at his own expenses accommodation for his employees/labours including adequate sanitary and water supply arrangements.
9. **Contractor should registered their labour in Labour Department, Uttarakhand and 1% Cess should be deducted from each running bill as per Gazette Notification No. 474(2)/VIII/12-35 (Shram)/2011, Dehradun dated 17-05-2012 by Employment Department of Uttarakhand Govt.**
10. **Contractor should submit copy of Income Tax return certificate for last financial year.**
11. **Eligibility- Contractor having similar works experience in the field of Horticulture & Attached a Certified copy of similar work done or ongoing works in any Development Authority of Uttarakhand or under government / semi government organization of Uttarakhand.**
12. All the materials to be used in work shall full-fill physical and other requirements as per the specifications and shall be approved by the engineer-in-charge. The contractor shall make all arrangements and shall provide such facilities as the engineer-in-charge may require for collecting, preparing, forwarding the required number of samples for tests and for testing of material. Nothing extra shall be paid for the above and including cost of materials to be tested. The testing charges if any shall be borne by the Contractor.
13. All materials arranged by the contractor shall be as per P.W.D specification and rejected materials if any will have to be removed by the contractor within three days from the site of the work otherwise these shall be removed from the site of the work by the department itself on contractor's cost. Also a penalty of 200/- per day shall be imposed till the materials are removed from the site by the Contractor.





14. An order book will be kept at the site of the work in which instruction shall be rendered by Engineer-in-charge or his representative. The contractor or authorized agent will be required to sign the order book daily for acknowledgement of the instruction. It is the responsibility of the contractor to examine the register and if he doesn't it shall be deemed to have been communicated to him.
15. The contractor should install at his own cost necessary water pumps, concrete mixer, pug mil machine conveyer and provide necessary vibrates suitable for R.C.C. work and this will be covered by his rates for respective items. In case of certain mechanical T&P etc. is available with the Deptt. The same may be issued at the discretion of Secretary as existing rule/rates of the deptt.
16. The contractor will have to intimate in writing to the Eng. I/C his program of laying slab and other important items of work at least 8 days before the commencement of laying so that the Engr. I/C may be able to check his program of supervision of the work. Any such items laid in the absence of Engr. I/C shall be rejected and the contractor will have to do the work again at his own cost. The work of reinforcement shall have to be got examined, by the Engr. I/C before deciding the date of the laying concrete.
17. As soon as the tender is accepted the contractor shall have to notify the name of his two authorized representative one of whom will always be available at site of work and the other for issue of materials and other misc. works. The contractor shall be responsible for the materials and order received by these two agents.
18. Any claims arising out during the period of contract will be submitted in writing as per the time line defined in GPW form 9 when such claims arise failing which the claims may not be entertained.
19. On completion, site of the work will be dressed and cleared all earth and waste materials etc by the contractor.
20. The contractor shall give his complete postal address below at the place specified for the purpose. Any changes in his postal address be intimated to authority receiving the tender. In case any communication dispatched to his given address is received back undelivered then in that case contents of the letter shall be binding on the contractor.
21. District Level Development Authority (DLDA), Udham Singh Nagar reserves the right to accept/reject any or all tenders without assigning any reason thereof.
22. One contractor or firm of the contractors should submit not more than one tender.
23. Power is reserved to accept tender for part work only and in such cases time for completion will be reduced to the extent considered reasonable by the accepting authority.
24. Contractors are not allowed to make any additions or alterations in tender papers. If any one does so the same will not be considered or the tender will be rejected.
25. That the DLDA, Udham Singh Nagar on satisfactory completion of the construction work shall make final payment as per M.B. and amount of 5% of the estimated cost will be



deducted subsequently from running bills. The amount of security money shall, if not withheld on account of breach of contract be refunded after six months of the date of completion of the work or after payment of the final bill, whichever is later subject to the condition that in case of building works the first rainy season comprising of months of June, August and September is not fully covered within the period of six months mentioned above. The amount of security money, if not withheld on account of breach of contract, be returned after expiry of the first rainy season comprising of the months mentioned above or after the payment of the final bill whichever is later.

26. That in case of any dispute between the DLDA, Udham Singh Nagar and the Contractors as regards construction, arising from the terms and conditions of this deed, the dispute shall be referred to Arbitrator as per the provisions of the Arbitration and Conciliation Act, 1996, AND the Arbitrator shall be the "Commissioner Kumaon Mandal, Nainital" whose decision shall be final and binding on both the parties.
27. Performance security shall be applicable as per Latest Government Order and according to Uttarakhand Procurement Rule.
28. The Earnest Money for the Tender may be in the form of NSC/FDR which should be pledged in favor of Security, District Level Development Authority Udham Singh Nagar. Tender without E.M.D and without a Non Judicial Stamp Paper of Rs. 100.00 affix one rupees revenue stamp on it and signed by the tenderer for the validity of tender will not be considered.
29. Tender has to provide an affidavit on a stamp paper of Rs. 100.00 that he has not been black listed from any Government /Private organization.
30. Defects Liability Period 04 (Four) Month from the Completion of Work.

**Contractor**

  
**Officer Inviting Tender**

**Bill Of Quantity**  
**DISTRICT LEVEL DEVELOPMENT AUTHORITY**  
**VIKAS BHAWAN COMPOUND, FIRST FLOOR, RUDR PUR, UDHAM SINGH NAGAR, UTTARAKHAND**  
Website : [www.ddausn.org.in](http://www.ddausn.org.in) E-mail : [udausnagar@gmail.com](mailto:udausnagar@gmail.com)

**Landscaping & Beautification of Indira Chowk, D.D. Chowk & Plantation Work at Matkota Tiraha to D.D. Chowk, Rudrapur**

S.NO	ITEMS	DSR CODE	QTY	UNIT	RATE	ADD 5% C.I	RATE WITH C.I	AMOUNT
1	Uprooting rank vegetation and weeds by digging the area to a depth of 60 cm, removing all weeds and other growth with roots by forking repeatedly, breaking clods, rough dressing, flooding with water, uprooting fresh growths after 10 to 15 days and then fine dressing for planting new grass, including disposal of all rubbish with all leads and lifts.	2.12	632.16	Sqm	53.60	2.68	56.28	35577.96
2	Supplying and stacking of good earth at site including royalty and carriage upto 5 km lead complete (earth measured in stacks will be reduced by 20% for payment).	2.2	315.64	Cum	469.50	23.47	492.97	155601.05
3	Supplying and spreading of sand in Lawn area, including watering, mixing and dressing complete.	2.27	22.608	Cum	1006.25	50.31	1056.56	23886.71
4	Digging holes in ordinary soil and refilling the same with the excavated earth mixed with manure or sludge in the ratio of 2:1 by volume (2 parts of stacked volume of earth after reduction by 20% : 1 part of stacked volume of manure after reduction by 8%) flooding with water, dressing including removal of rubbish and surplus earth, if any, with all leads and lifts (cost of manure, sludge or extra good earth if needed to be paid for separately)	2.14.2	456	No.	130.40	6.52	136.92	62435.52
5	Trenching in ordinary soil up to a depth of 60 cm including removal and stacking of serviceable materials and then disposing of surplus soil, by spreading and neatly levelling within a lead of 50 m and making up the trenched area to proper levels by filling with earth or earth mixed with sludge or / and manure before and after flooding trench with water (excluding cost of imported earth, sludge or manure).	2.1	675	Cum	68.70	3.43	72.13	48687.75
6	Filling mixture of earth and sludge or manure in the desired proportion in trenches, flooding with water and leveling (cost of supplying earth and sludge or manure and mixing excluded).	2.20	180	Cum	16.05	0.80	16.85	3033.00
7	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	2.31	11880	Sqm	10.80	0.54	11.34	134719.20

*(Signature)*



8	Providing & laying Selection no. 1 doob grass turf with earth 50mm to 60mm thickness of existing ground prepared with proper level and ramming with required tools wooden and than rolling the surface with light roller make the surface smoothen and light watering the same maintenance for 30 days or more till the grass establish properly, as per direction of officer in charge	2.34	452.16	Sqm	84.35	4.21	88.56	40043.29
9	Supply and Mixing Vermicompost	Mkt Rate	13300.00	Kg	10.00	0.00	10.00	133000.00
10	Providing and stacking of Foxtail palm of ht. 240-270 cm bottom girth 35-40 cm well developed in big size HDPE bags as per direction of the officer-in-charge.	7.44	11	No.	650.00	32.50	682.50	7507.50
11	Providing and Displaying Washingtonia filifera palm well developed 90 to 105 cm ht. having 5 to 6 straight fresh and healthy leaves in 35 cm Cement Pot as per direction of the officer-in charge.	5.44	19	No.	538.15	26.90	565.05	10735.95
12	Providing and Displaying Bismarckia Palm 115 to 180 cm ht., well developed 12 and above good color fresh and healthy leaves in 40 cm Cement Pot as per direction of the officer-in charge	5.11	26	No.	1937.25	96.86	2034.11	52886.86
13	Providing and stacking of Nerium oleander (kaner) dwarf of height 30-40 cm. in earthen pot of size 20 cm as per direction of the officer-in-charge.	8.51	15000.00	No.	40.00	2.00	42.00	630000.00
14	Providing and stacking of Murraya exotica of height 45-60 cm. in poly bags of size 15 cm as per direction of the officer-in-charge.	8.46	2000.00	No.	15.00	0.75	15.75	31500.00
15	Providing and stacking of Delonix regia (Gulmohar) of height 12 to 15 ft. in big poly bags of 21 inches x 21 inches as per direction of the officer-in-charge.v	Mkt rate	70	No.	650.00	32.50	682.50	47775.00
16	Providing and stacking of Cassia fistula (Amaltas) of height 12 to 15 ft. in big poly bags of 21 inches x 21 inches as per direction of the officer-in-charge.v	Mkt rate	70	No.	1000.00	50.00	1050.00	73500.00
17	Providing and stacking of Jacranda Mimosifolia of height 12 to 15 ft. in big poly bags of 21 inches x 21 inches as per direction of the officer-in-charge.v	Mkt rate	70	No.	650.00	32.50	682.50	47775.00
18	Providing and stacking of Bahunia Purpurea (Kachnar) of height 12 to 15 ft. in big poly bags of 21 inches x 21 inches as per direction of the officer-in-charge.v	Mkt rate	70	No.	900.00	0.00	900.00	63000.00

*[Handwritten signature]*



19	Providing and stacking of Cassia Samiea of height 12 to 15 ft. in big poly bags of 21 inchs x 21 inchs as per direction of the officer-in-charge.v	Mkt rate	70	No.	750.00	0.00	750.00	52500.00
20	Providing and stacking of Michelia Champaca of height 12 to 15 ft. in big poly bags of 21 inchs x 21 inchs as per direction of the officer-in-charge.v	Mkt rate	70	No.	1050.00	0.00	1050.00	73500.00
21	Providing and stacking of Tabernaemontana coronaria (chandni variegated) of height 45-60 cm. with 3-4 branches earthen pots of size 20 cm as per direction of the officer-in-charge	8.61	50	No.	45.00	2.25	47.25	2362.50
22	Providing and stacking of Tecoma stans of height 45-60 cm. branched in earthen pots of size 20 cm as per direction of the officer-in-charge	8.70	50	No.	45.00	2.25	47.25	2362.50
23	Providing and stacking of Plumbago capensis well developed with fresh and healthy 30 to 45 cm ht., with bloom in 20 cm Earthen Pot/Plastic Pot as per direction of the officer-in-charge	8.55	50	No.	60.00	3.00	63.00	3150.00
24	Providing and stacking of Chandni dwarf of height 15-20 cm., well branched in earthen pots of size 20 cm as per direction of the officer-in-charge. s per direction of the officer-in-charge	8.14	50	No.	35.00	1.75	36.75	1837.50
25	Providing and displaying of Raphis Palm having ht. 75 cm to 90 cm with 15 to 18 equal suckers, well developed, full of fresh and healthy leaves from bottom to top in 35 cm PVC Pots/C.Pots & as per direction of the officer-in-charge.	3.77	80	No.	353.65	17.68	371.33	29706.40
26	Plantation of Trees, Shrubs, and Hedge at site i/c watering and removal of unserveiceable material's as per direction of officer in charge (excluding cast of plant & water	2.57.2	17280	No.	3.65	0.18	3.83	66182.40
27	Plantation of Trees, Shrubs, and Hedge at site i/c watering and removal of unserveiceable material's as per direction of officer in charge (excluding cast of plant & water	2.57.1	476	No.	7.3	0.365	7.67	3648.54
	Green Belt along the highway from Vikas Bhawan to DD chowk							
28	Complete maintenance of Trees 420 (Out side garden features), jobs like making of basin at regular interval i/c watering, weeding, pruning & application of fertilizer etc, as per direction of officer in charge Green Belt along the highway from Vikas Bhawan to DD chowk (As per Analysis)	15000.00		For all Plants Per Month for 03 Months				45000.00

*[Handwritten signature]*

